FINISH NOTES (VERIFY W/ OWNER)

1. ALL FINISHES TO MEET REQUIREMENTS OF CHAPTER 8 OR THE STATE OF WISCONSIN ENROLLED COMMERCIAL BUILDING CODE

DOOR AND HARDWARE NOTES:

1. ALL DOORS TO HAVE 1 1/2 PAIR BUTTS (MIN.)
2. ALL DOORS WIDER THAN 3'-4" OR TALLER THAN 8'-0" TO HAVE 2 PAIR
3. ALL EXTERIOR BUTTS TO HAVE NON-REMOVABLE PINS
4. THRESHOLDS REQUIRED FOR CHANGES IN FLOOR MATERIAL NOT INDICATED
5. ALL LOCKSETS TO HAVE LEVER HANDLES (VERIFY STYLE)
6. ENTRANCE LOCKSETS ON EXTERIOR DOORS, PRIVACY LOCKSETS ON TOILET ROOMS, STORE ROOM LOCKSET ON UTILITY ROOM.
7. VERIFY CLOSER TYPES AND LOCATIONS
8. MINIMUM DOOR SIZE 3'-0" X 6'-8"
9. VERIFY NEW BORROWED LIGHT WINDOW SIZES AND LOCATIONS ALL GLAZING TO BE TEMPERED
10. ALL DOORS TO BE FLUSH WOOD W/ H.M. FRAMES UNLESS NOTED OTHERWISE STAINED & VARNISHED DOORS - PAINT FRAMES

(2) EXISTING H.C. PARKING SPACES
INSTALL NEW SIGNS PER DETAILS ON SHEET 61

SUITE "B" 4,000 SQ/FT

SUITE "A" 10,700 SQ/FT

EXISTING OFFICE
EXISTING OFFICE
EXISTING OFFICE
EXISTING OFFICE
EXISTING TANNING
EXISTING TANNING
EXISTING UTILITY
EXIST. TOILET
MOVABLE 7" H. PLATFORM CONSTRUCTED OF 2X8 WOOD JOIST AT 2'-0" O.C W/ 3/4" OSB SHEETING (CARPETED)
EXISTING GENERAL FITNESS ROOM
PROP. CLOSET
REMOVE EXISTING HALF WALLS
EXISTING WOMENS FITNESS ROOM
NEW PARTITION WALL 5/8" DRYWALL EACH SIDE OVER 3 5/8" MTL. STUDS AT 16" O.C.
ELEC.
VEST.
STEAM ROOM INSTALL NEW WALL & FLOOR TILE
REMOVE & RELOCATE EXISTING LOCKERS & WOOD BENCHES
EXISTING CLOSET
ADD RECESSED WALL OPENINGS BELOW EXISTING T.V. LOCATION
TANNING ROOM
EXISTING LOCKER ROOM
EXISTING SAUNA
EXISTING SHOWER
EXISTING RESTROOM
EXIST. CLOSET
HOT TUB AREA
EXISTING SHOWER
EXISTING RESTROOM
NEW 3'-0" X 7'-0" DOORS & FRAMES
EXISTING LOCKER ROOM
RELOCATED LOCKER AND WOOD BENCH
REMOVE EXISTING LOCK AS REQUIRED
EXISTING VESTIBULE
NEW SERVICE COUNTER
PROPOSED LOUNGE
REMOVE EXISTING SERVICE COUNTER
REMOVE EXISTING WALL
EXISTING OPEN AREA 6654 S.F.
NEW STAIR W/ LEVEL LANDING
PROPOSED WATER WALL
EDGE OF MEZZANINE ABOVE
EXISTING WEIGHT AREA
EXERCISE ROOM
1 HOUR FIRE RATED STAIR ENCLOSURE 5/8" DRYWALL OVER 3 5/8" MTL STUDS AT 16" O.C. PER UL DESIGN #U465 UP TO UNDERSIDE OF EXISTING ROOF
EXISTING CARDIO THEATER BELOW
5'-0"X 7'-0" WOOD DOOR & H.M. FRAME W/ CLOSER & 60 MINUTE RATING
NEW 3'-0" X 7'-0" DOORS & FRAMES
REMOVE EXISTING WALLS, DOORS & FRAMES
RE-OPEN EXISTING HOT TUB
STORAGE
TANNING ROOM
REMOVE & RELOCATE EXISTING LOCKERS & WOOD BENCHES
54'-0"
110'-0"